



Design, Material Selection and Operational Feedback for the New Design of the High Energy Beam Dump in the CERN SPS

P. Rios-Rodriguez, A. Perillo-Marcone
M. Calviani (CERN)





ENGINEERING
DEPARTMENT

Contents

- Introduction of the SPS beam dump (TIDVG)
- Previous SPS beam dumps
 - Design of TIDVG#3 (2014-2016)
 - Post-mortem inspection of TIDVG#3 (July 2017)
 - History of the SPS beam dumps
- Current SPS beam dump - TIDVG#4
 - Design
 - Material selection
 - Assembly and installation
 - Operational feedback for TIDVG#4
- Future SPS beam dump (TIDVG#5)
 - Design
 - Prototyping activities
- Conclusions

Introduction of the SPS beam dump

CERN's Accelerator Complex





Two beam dumps in the SPS:

- **TIDH** (Target Internal Dump Horizontal): <28 GeV
- **TIDVG** (Target Internal Dump Vertical Graphite): >105 GeV
 - Total length 4.3 m, 30 cm core diameter
 - Internal dump (in UHV)


Beam dilution on dump

- In order to avoid damaging the dump material, the beam is diluted during $\sim 7.2 \mu\text{s}$ with dilution/extraction kickers
- Asymmetry in the energy deposition in the dump induced by the position of the dump with respect to the injected beam



Previous SPS beam dump - TIDVG#3

Operating during 2014-2016




Background for TIDVG#3 inspection

- Leak in the TIDVG sector appeared on April 25th 2016 after a series of dumps at high energy
- Helium spray vacuum leak tests in the tunnel indicated leak in the core inside outer shielding
- Slow increase of vacuum pressure over the rest of the year (10^{-8} mbar \rightarrow 10^{-6} mbar)
- Replaced with TIDVG#4 before 2017 run
- TIDVG#3 stored in bunker
- Post mortem inspection recommended from beginning of crisis project



Aim of post mortem investigations

- In general - learn from this failure to improve future designs
- Confirm source of vacuum leak – 3 main possibilities:
 - Core longitudinal electron beam welds
 - Lift point holes at top of core
 - Thermocouple holes at bottom of the core




Inspection method

- Remote handling needed as dose rates expected of several tens mSv/h with shielding open
- Initially considered removing core from shielding to inspect whole surface
- However, to simplify handling and reduce risks – lift upper shielding only to access top half of core and longitudinal welds





Preparation

- CATIA sequence to check feasibility and organize with teams
- Prepare work dose planning (consider recovery from problems)
- Mock-up trials on identical shielding to develop techniques for key tasks using mobile robots and crane:
 - Lifting mobile robots
 - Undoing shielding bolts (six M36 threaded bars with nuts)
 - Lifting upper shielding
 - Vacuum leak testing
 - Replacing shielding bolts




Inspection operation

- Operations went well
- Personnel radiation doses less than estimate (102 μSv vs 180 μSv)
- Leak testing was able to identify leak points
- Visual inspection showed weld condition
- Note: shielding opened 3x (1x in WDP)




Findings

- Vacuum leaks were present on both longitudinal welds around half way the core
- The electron beam welds in the areas where leaks were found showed evidence of re-work
- Situation worsened by the fatigue (dump bending)



Visual inspection – weld close ups




Inspection conclusions

For the TIDVG:

- Longitudinal electron beam welds along the core were identified as the source of the leak
- Positions of the leaks correspond to the areas of some of the weld re-work and the highest tensile stresses

The new TIDVG#4 and #5 use a seamless stainless steel tube to avoid these welds!



For the remote investigation:

- Mock-up work ensured full development of operating methods, tools, hardware and efficient collaboration between different teams
- Remote vacuum leak testing allowed leaks to be pinpointed
- Remote visual inspection identified areas of weld re-work
- Careful operation and reliability of commercial and in-house robots ensured no major problems with remote operations

Ex. what happened to a previous TIDVG#2




- Molten Al due to beam impact
- Affected area much larger than beam size
- Culprit was the thermal contact conductance between Al and the heat sink



History of the SPS beam dump


| Device | Modifications/Experience | Date |
|---------|---|-----------|
| TIDVG 1 | Molten Al + Ti (outgassing!) | 2000-2004 |
| TIDVG 2 | Molten Al (outgassing!) | 2006-2013 |
| TIDVG 3 | Longer Gr (+200 mm), shorter Al Vacuum leak in April 2016- NO SPARE! | 2014-2016 |

- After the vacuum leak in April 2016:
- **New design** → **TIDVG#4** for 2017-2018 operation (previous design: extremely long manufacturing times)
- Weak points of TIDVG1, 2 and 3:
 - High outgassing rates
 - No proper bake-out possibilities after installation
 - No internal instrumentation
 - High uncertainty of cooling efficiency



Current SPS beam dump – TIDVG#4

Installation during EYETS 2017 (March)



- Limited time window:
 - Faster manufacturer, COTS materials
 - Use of known technologies. No R&D
 - 0.2 MPa (27 kN/m)
- T sensors on all the parts (18 in total)
- T sensors for the water +1 flow meter
- Copper core made of CuCrZr

Material selection for TIDVG#4

- General material requirements for the SPS beam dump design:
 - **Good thermal and mechanical properties**
 - High power to be dissipated and high stresses due to the beam impact
 - Materials available in needed quantities, sizes and easy to machine + delivery
 - **UHV compatibility** including avoid all welds
 - **Avoid Al** (molten in previous design)

| Component | CERN specifications | Additional treatments applied |
|-------------------------|---|--|
| Graphite | Homogeneity Isotropic properties Grade with low E and high tensile strength | Degreased Purified in Ar @ $T > 2000^{\circ}\text{C}$ Vacuum fired @ 950°C at CERN |
| Tungsten alloy | Homogeneity | Degreased at CERN Vacuum fired @ 950°C at CERN |
| CuCrZr | Homogeneity / 3D forged | Degreased at CERN |
| Tube for vacuum chamber | Homogeneity + small grain size 3D forged 316L as per CERN spec. Seamless | Degreased at CERN |

Current SPS beam dump – TIDVG#4

Forging of SS vacuum chamber



SS vacuum chamber




Vacuum firing of the Gr blocks

Tungsten alloy



CuCrZr core



Current SPS beam dump – TIDVG#4


Graphite inside the
CuCrZr core




Medium/high-Z absorber




TIDVG#4 core fully assembled and
ready for insertion in the vacuum
tube



TIDVG#4 core being pulled
into the vacuum chamber



Final leak detection
(upstream/ water manifolds)




TIDVG#4 core fully
inserted (upstream)




Current TIDVG#4 Installation

Installation during EYETS 2017 (March)



Operational feedback for TIDVG#4

Performance monitoring



| | |
|---------------------------|---------|
| P-VACUUM-VGHB11860 (mbar) | 7.00e-8 |
| P-VACUUM-VGHB11879 (mbar) | 1.90e-7 |
| P-VACUUM-VGHB11931 (mbar) | 1.10e-8 |

| | |
|---------------------------|---------|
| P-VACUUM-VGHB11936 (mbar) | 1.60e-9 |
| P-VACUUM-VGHB11952 (mbar) | 6.00e-9 |
| P-VACUUM-VGHB11959 (mbar) | 1.80e-8 |


Beam intensity: 7.63e+11 charges

Beam energy: 4.00e+2 GeV

Average beam power over last 10 mins: 4.27e+1 kW

Average beam power over last 10 SC: 4.83e+1 kW


Average beam power over last hour: 1.88e+1 kW



Gr583-RD


14 PT100 installed in the dump core
(2 PT100 were damaged during assembly)

Operational feedback for TIDVG#4



4 PT100 on the SS vacuum chamber
2 PT100 on the shielding

Operational feedback for TIDVG#4



Sensors located in the water:

- 2 flow-switches
- 4 PT100 in the water
- 1 water flow sensor (water flow and outlet T)


Operational feedback for TIDVG#4

| Beam Type | p GeV/c | Bunch Intensity (protons) | # Bunches | Total Intensity (protons) | Continuous beam dump | Average power (kW) |
|-----------|------------|---------------------------------|--------------|---------------------------------|-------------------------|--------------------------|
| LHC | 440 | $1.10 \cdot 10^{11}$ | 48 | $5.3 \cdot 10^{12}$ | 2h30 | 9 |
| LHC | 440 | $1.25 \cdot 10^{11}$ | 72 | $9.0 \cdot 10^{12}$ | 4h00 | 16 |
| LHC | 440 | $1.10 \cdot 10^{11}$ | 144 | $1.6 \cdot 10^{13}$ | 3h00 | 27 |
| LHC | 440 | $1.10 \cdot 10^{11}$ | 288 | $3.2 \cdot 10^{13}$ | 1h30 | 55 |





- Dedicated **commissioning beams** have been requested in order to validate the performances of the dump (cross-check with simulations) as well as to condition the graphite
- TIDVG4 is designed for continuous deposited power of **~60 kW**

Operational feedback for TIDVG#4



Behavior under 48b beam





Operational feedback for TIDVG#4



Operational feedback for TIDVG#4




Good agreement (within ~25%)




Operational feedback for TIDVG#4


~Steady state at **144 bunches** (27 kW deposited)




Simulation for **27 kW**
(**144 bunches** x $1.1 \cdot 10^{11}$
 $I_{\text{total}} = 1.6 \cdot 10^{13}$)



288 bunches (1h30– 55 kW deposited)




Simulation for **56 kW**
(**288 bunches** x $1.1 \cdot 10^{11}$)




Future SPS beam dump (TIDVG#5)


- TIDVG5 must be capable of dissipating **~200 kW** average deposited power
- To be installed in SPS by 2020 (during LS2)



Future SPS beam dump (TIDVG#5)




- A ventilated large shielding assembly will surround the dump core




Future SPS beam dump: prototypes

HIP of cuprous materials around SS pipes (Fraunhofer): the contact between the tubes is made by diffusion bonding, i.e. perfect contact.



On-going prototyping activities:



- Real length prototype
- Cooling performance will be tested
- CuCrZr material characterization will be performed after HIP and thermal treatments
- Study of the interface CuCrZr-SS tube

M. Calviani 22/09

Conclusions

- TIDVGs are critical components of the CERN's accelerator complex
- TIDVG#4 successfully installed and operational according to the project schedule
- Good vacuum performance with a fast conditioning observed
- Good thermal performance (tested for high power beams)
- Longitudinal electron beam welds along the core were identified as the source of the TIDVG#3 leak and must be avoided for future designs (using a seamless vacuum chamber)
- Lessons learnt for TIDVG#5 design (installation in 2020)



ENGINEERING
DEPARTMENT

Thank you for your attention.

Do you have any questions?

Acknowledgements: J. A. Briz, K. Cornelis, R. Esposito, S. Gilardoni,
B. Goddard, J.L. Grenard, D. Grenier, M. Grieco, J. Humbert, V. Kain, F. Leaux,
S. De Man, C. Pasquino, J. R. Poujol, S. Sgobba, D. Steyaert, F. M. Velotti,
V. Vlachoudis