


# LCLS-II SRF commissioning and early operational experience

ERL2024 KEK, WG-3



Sebastian Aderhold, for the LCLS-II commissioning and  
operations team

September 27, 2024

# Outline

Facility Overview

SRF commissioning

Early operational experience

Outlook

Summary

Remove SLAC Linac from Sectors 0-10

New Cryoplant

New Injector and New Superconducting Linac

Existing Bypass Line

New Transport Line

Two New Undulators And X-Ray Transport

Reconfigure Near Experiment Hall

- LCLS-II design features:**
- CW VHF gun
  - CW SRF linac
  - Support MHz-rate
  - Two undulator lines
  - Pulsed magnetic kicker
  - Long (2km) bypass line
  - Machine protection and beam loss control

# LCLS-II

BERKELEY LAB

Fermilab


Argonne NATIONAL LABORATORY

Jefferson Lab

SLAC NATIONAL ACCELERATOR LABORATORY

Stanford University

U.S. DEPARTMENT OF ENERGY



# LCLS FEL complex based on normal and superconducting Accelerators


## Superconducting Linac

4 GeV, High rep-rate, CW RF

Future 8 GeV extension (LCLS-II-HE)



Soft and Hard X-ray Variable Gap Undulators (VGUs)



*Linac gallery and new cryoplant viewed from Sector 0*



## Normal Conducting Linac

3.5-17 GeV,  
120 Hz Pulsed RF

# LCLS-II Key Performance Parameters - KPPs

Performance Measure	Threshold (5 kW beam)	Objective (120 kW beam)	Measurements
Variable gap undulators	2 (soft and hard x-ray)	2 (soft and hard x-ray)	
<b>Superconducting linac-based FEL system</b>			
Superconducting linac electron beam energy	3.5 GeV <input checked="" type="checkbox"/>	≥ 4 GeV	Spectrometer bend (magnet strength, screen)
Electron bunch repetition rate	93 kHz <input checked="" type="checkbox"/>	929 kHz	BPM's, laser rate
Superconducting linac charge per bunch	0.02 nC <input checked="" type="checkbox"/>	0.1 nC <input checked="" type="checkbox"/>	Toroid, Faraday cup
Photon beam energy range	250–3,800 eV <input checked="" type="checkbox"/>	200–5,000 eV	Absorption edges, spectrometer
High repetition rate capable end stations	≥ 1 <input checked="" type="checkbox"/>	≥ 2 <input checked="" type="checkbox"/>	N/A
FEL photon quantity ( $10^{-3}$ BW) per bunch	$5 \times 10^8$ (10x spontaneous) @2,500 eV <input checked="" type="checkbox"/>	$> 10^{11}$ @ 3,800 eV	Gas energy monitor, GMD, Spectrometer
<b>Normal conducting linac-based system</b>			
Normal conducting linac electron beam energy	13.6 GeV <input checked="" type="checkbox"/>	15 GeV <input checked="" type="checkbox"/>	Spectrometer bend (magnet strength, screen)
Electron bunch repetition rate	120 Hz <input checked="" type="checkbox"/>	120 Hz <input checked="" type="checkbox"/>	BPM's, laser rate
Normal conducting linac charge per bunch	0.1 nC <input checked="" type="checkbox"/>	0.25 nC <input checked="" type="checkbox"/>	Toroid, Faraday cup
Photon beam energy range	1–15 keV <input checked="" type="checkbox"/>	1–25k eV <input checked="" type="checkbox"/>	Absorption edges, spectrometer
Low repetition rate capable end stations	≥ 2 <input checked="" type="checkbox"/>	≥ 3 <input checked="" type="checkbox"/>	N/A
FEL photon quantity ( $10^{-3}$ BW <sup>a</sup> ) per bunch	$10^{10}$ (lasing @ 15 keV) <input checked="" type="checkbox"/>	$> 10^{12}$ @ 15 keV	Gas energy monitor, GMD, Spectrometer

# Outline

Facility Overview

**SRF commissioning**

Early operational experience

Outlook


Summary

# SRF Commissioning

## SRF commissioning was very successful


- 97% of all cavities fully operational (planned for 94%)
- Total commissioned (summed individual cavity) voltage exceeded design by >20% and reached 4.8GV
- No significant change in field emission observed with respect to cryomodule acceptance tests at partner labs

### Gradient Performance



# Gradient Performance

## Comparison with Acceptance Test




Admin limits:

- 18 MV/m in commissioning
- 21 MV/m in acceptance test


- Gradient performance is in line with CM acceptance test measurements at FNAL and Jlab
- No observable change in field emission onsets or magnitude from installation
- Multipacting processing resulted in  $\sim 3$  MV/m gain in stable gradient

## Change in FE Onset






# Undulator and FEL commissioning



- Beam-based alignment with Cu-linac beam;
- E-beam transverse and longitudinal optimization;
- Beam loss control; Undulator tapering;
- GMD, spectrometer, XTCAV measurement.



First lasing with SC-linac beam, **SXR line, 8/23/2023; HXR line, 9/6/2023**



XTCAV and XTCAVB to support commissioning

# Beam Repetition Rate

- Achieved 10 kHz beam rate on 12/9/2022.
- Achieved 93 kHz (6/7/2023)
  - → Project Threshold Milestone
- *Initial science program operates at 8.25 kHz.*
- While ramping up the beam rate:
  - Diagnostic devices response
  - Feedback system response
  - Machine protection system
  - Beam loss monitor display
  - Beam dump and cooling water temperature response
  - Verify actual beam rate with Toroid or BPM BSA data



# Outline

Facility Overview


SRF commissioning

**Early operational experience**

Outlook

Summary

# Beam Stability



6/23/2024  
65pC, 8kHz, 530eV:  
operation data in 4 hours

## Design jitter specs (rms):

charge jitter: 1.5%,  
energy jitter: 1e-4,  
peak current jitter: 4%,  
arrival time jitter: 20 fs.

With the 3<sup>rd</sup> cathode


# Cavity availability

- After initial commissioning only 3% of cavities non-operational (problems inside the CM that need room temperature warm-up)
- No additional cavities with problems inside cryomodule since then
- All new problems related to LLRF system, cables/connections or SSAs
- Individual Solid State Amplifiers allow to take single cavities with intermittent problems offline for maintenance
- Generally enough amplitude overhead to compensate for cavities being repaired while the linac is running or during maintenance periods




# Offline cavities over time

- During operation cavities with problems are taken offline to be fixed later.
- Repair during maintenance periods or parasitically (if possible)
- 9 cavities (3%) offline due to long term issues
  - power coupler: 2x
  - Tuner (stepper/ piezo/ limit switch): 7x
  - Will require linac warm-up
- Remaining cavities mostly RF-system related



# Cryogenic system is very robust


- Electric heaters on underside of cavity helium vessels to compensate for change in RF heatload
- Control loop regulates linac helium pressure by adjusting electric heaters to keep return pressure to cold compressors stable
- Even in cases of sudden loss of all RF heat [e.g. shut-off by Personal Protection System (PPS)] feedback keeps cold compressors stable and recovers pressure within minutes



# Software development and automation

## Auto Setup GUI


- Push-button tool for initial set-up or to address cavities that have become unstable
- Building heavily on software framework developed for and since initial linac commissioning
- Simplified interface on top of expert screens for ease of operator use
  - Automated sequence of steps, some level of error handling and checking if values are within set boundaries
- Start of the whole linac (e.g. after maintenance days) CM by CM within 30min - 1h, depending on number of parallel instances
- Recent infrastructure improvement cut down to less than 5min, true single button





# Microphonics

- Overall microphonics levels are very good
  - 94% of cavities within specification of +/-10Hz
- Only two cavities are currently amplitude limited due to microphonics
- Biggest source of excessive microphonics are cooldown valve leaks
- More details by R. Porter at SRF2023: MOPMB081



# L3 insulating vacuum

## Upstream linac section

- L3 string is separated into section upstream and downstream of insulating vacuum break
- L3 upstream string exhibits higher than expected static heatload and increased insulating vacuum pressure
  - Suspect leak from helium process pipe into insulating vacuum space
  - Partially mitigated by doubled pump capacity


	EXPECTED CM STATIC	OBSERVED CM STATIC (Initial)	OBSERVED CM STATIC (with Additional Pump)
LO-L2	9 W / CM → 150 W	9 W / CM → 150 W	9 W / CM → 150 W
L3-UPSTREAM	9 W / CM → 90 W	47 W / CM → 470 W	17 W / CM → 170 W
L3-DOWNSTREAM	9 W / CM → 90 W	16 W / CM → 160 W	16 W / CM → 160 W
<b>TOTAL CM STATIC</b>	<b>330 W</b>	<b>800 W</b>	<b>500 W</b>



# L3 insulating vacuum

## Downstream section

- L3 downstream string insulating vacuum pressure has oscillating behavior
  - Oscillation period is dependent on whether RF is on (~1.5h) or off (~3h)
  - Global heater feedback reacts in response to change in static heatload
  - Suspect leak in cooldown line of one of the later CMs (~CM33-34)
  - Most notable consequence is HOM couplers on some cavities to start (over-) heating
    - Decreased cavity amplitudes slightly to accommodate



# New Field Emission in CM01

---


- CM01 has specific cavity amplitude requirements for optimal injector performance and linac beam quality
  - Cryomodule with high max amplitudes and without field emission was chosen for this location
  - For best emittance preservation cavity 1 runs at low amplitude (6.5MV) and cavity 2 is chosen to be off
- Prompted by unexplained high signals on beam loss monitors in injector moved radiation monitors next to CM01 and re-characterized field emission
  - Found field emission in cavities 2, 3, 4, 5
- No specific events in beamline vacuum that would explain particle migration or gas bursts

# CM01: Path forward

---

- Will keep monitoring field emission levels in CM01 on a regular basis
- Started re-characterization campaign for all other CMs (moving one set of sensors every maintenance period)
- Assessing impact on injector performance
  - Just at the lower edge of required energy for laser heater operation while keeping cavities below 50mR/hr when turning on cavity 2
  - Seems feasible as long as FE does not get worse
- Looking for mechanisms that would explain pattern with highest radiation in the middle of the CM
- Long term solutions (both would need room temperature warm-up and significant work):
  - Replace cryomodule with spare
  - Perform in-situ plasma processing

# Change in cavity amplitude limits due to Field Emission (FE)



Total cavities in linac	296
Cavities re-characterized for FE	128 (43%)
Cavities with change in FE characteristics	12 (4%)
Number of affected CMs	7 (out of 16 re-characterized)
Cavities where the change impacts operational setpoint	7 (2%)

Total amplitude lost over whole linac: 45.4 MV

# Outline

Facility Overview

SRF commissioning


Early operational experience

**Outlook**

Summary

# Ramp-up Plan for 500 kHz FEL Operation – 120 kW Limit

- Current beam power limit is 5 kW (safety system limitation)
- Ramp – up to full performance is governed by safety system functionality, RP surveys, beam loss minimization.
- Process to achieve KPP's will take 2-3 (+) years and will be integrated into user program.
- Repetition Rate and Bunch charge can be traded to maintain a specific beam power.
- Critical concern is undulator dose rate → prevention of radiation damage of magnetic material.



Ramp-up is governed by beam power considerations, management of beam losses.



# LCLS-II-HE Construction is underway

## Double the electron energy of the accelerator (4 → 8 GeV)



- Extends X-ray energy range from 5 keV to 12.8 keV

## Provide a dual source X-ray capability

- Delivers simultaneous soft X-ray and hard X-ray beams at high repetition rate

## Provide specialized instrument for unique new source

- Delivers optimized measurement capabilities and enables science immediately after accelerator commissioning



Upgrade the X-ray Pump Probe (XPP) instrument for MHz beam and data rates and upgrade the photon transport optics and beamline components through the Hard X-ray instruments.

# Summary

---

- LCLS-II SRF commissioning has been a successfully completed and threshold key performance parameters have been met
- Early operations of SRF systems are going well (beam stability, microphonics, cavity availability) with some issues (new field emission in CM01, insulating vacuum in L3 string)
- Next year will be spent delivering beam to users in parallel to further beam performance improvement and beam power ramp up
- Getting ready of LCLS-II-HE installation