Summary WG 5 - Facilities

Hiroshi Sakai (KEK)


Michaela Arnold (TU Darmstadt)

Program

Status of cERL [TUO01]	Miho Shimada (KEK)
Kobayashi Hall, High Energy Accelerator Research Organization (KEK)	10:30 - 10:50
CBETA: Achievements, Challenges, Status, and Plans [TUO02]	Joseph Berg (Brookhaven National Laboratory)
Kobayashi Hall, High Energy Accelerator Research Organization (KEK)	10:50 - 11:10
Status of the S-DALINAC with focus on ERL operation [TUO03]	Michaela Arnold (TU Darmstadt)
Kobayashi Hall, High Energy Accelerator Research Organization (KEK)	11:10 - 11:35
Status of the ERL project bERLinPro: Final comissioning preparations [TUO	Axel Neumann (HZB)
Kobayashi Hall, High Energy Accelerator Research Organization (KEK)	11:35 - 11:55
MESA facility report [TUO05]	Timo Stengler (University Mainz)
WG5	11:55 - 12:20
Lunch	12:20 12:20
Kobayashi Hall, High Energy Accelerator Research Organization (KEK)	12:20 - 13:20
PERLE Status and Plans [TUO06]	Walid Kaabi (IJCLab-CNRS)
Kobayashi Hall, High Energy Accelerator Research Organization (KEK)	13:20 - 13:45
Progress on Terahertz Light Production at TRIUMF e-Linac [TUO07]	Hui Wen Koay (TRIUMF)
Kobayashi Hall, High Energy Accelerator Research Organization (KEK)	13:45 - 14:05
BriXSino: an ERL proposed facility at INFN Milan LASA Laboratory [TUO08]	Dario Giove (INFN-LASA)


Activity of cERL in FY2023






1) ~1mA (952µA) CW operation was successfully demonstrated

- With undulators & energy recovery without beam loss by using collimator and loss monitor
- 2) Machine learning for 1mA operation
 - For tuning QMs near the undulators
 - For collimator tuning before accelerating of main cavity






3) High bunch charge (60pC) beam ERL operation tried for FEL generation


CBETA

- Configurable to 4-pass, 150 MeV
- Permanent magnet FFA return loop
- 1-pass, reached 70 μA
- 4-pass at low current
- Challenges to overcome
 - Losses in 4-pass
 - RF stability
- Can run if funded






S-DALINAC: TAKE HOME MESSAGE




Efficiency




One-turn ERL operation

Three-turn

ERL study



Two-turn ERL operation



Experiment: Laser Compton Backscattering











300

Beam loading:

+ 1x dec. + 2x dec. = TER


2x acc. = CTA

Initial current (µA)

Axel Neumann




Current status of the bERLinPro facility




View from the injector line beam-dump towards the SRF photo-injector: Ready for beam commissioning

- Successful twice cooldown and follow-up RF test
 of the SRF photo-injector with field levels for beam energies ≥ 2 MeV
 and I_{avg}≤ 10 mA given by the RF coupler power limit (Jan-May 2024)
- Finalization of all required components for the injector characterization and first beam operation, e.g. diagnostics, cathode laser, photo-cathode transfer system
- Awaiting permit for beam operation starting from about mid of October
 2024

 Work on assembly of Booster has started and will come to full force, once the operation at bERLinPro starts



Timo Stengler




- First Beam! (100 keV)
- Most parts delivered/in delivery
- LINAC + Spin manipulation installed

Achievments:

Challenges:


- Cool down Cryomodules
- RF and system control
- Experimental Set-ups







PERLE PERLE Status and Plans:


- o Important progress on design phase, PERLE TDR release is foreseen on fall 2025.
- Staging approach adopted to build PERLE in respect to available funds & in-kind contributions. More funds are needed for the complete program.
- DC-gun + photocathode+ preparation chamber acquired from RI within a Collaboration Agreement.
- Construction of the LINAC cryomodule is supported by the European Program iSAS (with IN2P3 matching funds + CM vessel from ESS).
- Funds obtained within RI2 national program (CNRS). it secure the full injection line and a part of a first tour equipment construction.


















Later stages: Installation of a high-brightness photo-gun perpendicular to current low-

energy beamline to produce ~picoseconds pulsed beams with energy 500 keV or above.

Progress on Terahertz Light Production at TRIUMF e-Linac

E-gun








Dario Giove BriXSinO

ParameterValueEnergy (MeV)20-45Bunch charge (pC)50 - 200Repetition rate (MHz)100Average Current (mA)<5 $\epsilon_{n,x,y}$ (mm mrad)1.0energy spread (%)< 0.2


- A "newly" conceived scheme of ERL with counter propagating beams is proposed in BriXSinO.
- This scheme allows to explore not only the ERL operation but also the two-pass operation where the beam is reaccelerated when reinjected in the accelerating module at reduced current.
- A further operation mode for BriXSinO is the use of its injector for fixed target experiments performed with maximum electron energy of 10 MeV and 5 mA average current.
 - This high intensity beam enables both experiments of flash therapy (total charge in a 200 ms time interval up to 1 mC), as well as converting the electron beam into bremsstrahlung photons with energy peaked at 7 8 MeV at an impressive flux of 10¹⁶ photons/s (i.e. up to 30 kW X-Ray beam).
- Also experiments of **positronium generation** for fundamental studies of matterantimatter asymmetry can be conducted at this test station.


An ERL proposed facility at INFN -LASA Laboratory




- ✓ In September 2022, the first part of the accelerator, a **High Voltage photoinjector DC operated** followed by a couple of room temperature cavities, has been partly funded by INFN under the supervision of the **CSN5 Committee (HB2TF project)**.
- ✓ In October 2022, an additional funding was granted by INFN to complement an allocation made in 2021 for establishing a dedicated test stand for BriXSinO laser related research. Within this R&D, we obtained a maximum power of 30 kW in air in the Fabry-Perot prototype cavity.
- ✓ In March 2023, a **revised version of the original Technical Design Report** of BriXSinO has been discussed by the proposers and the INFN Milano Director with the INFN Executive Council, the chair of the INFN MAC and the INFN-Accelerator committee.
- ✓ As part of the PNRR-IRIS program and with a significant INFN specific contribution, in 2024, the construction of two laboratories will begin within the LASA premises:
 SML (Superconducting Magnet Laboratory) and AATF (Advanced Accelerator Test Facility) for a total of 2100 m² spread over an underground bunker and two external floors.
- ✓ In July 2023, a **Horizon Europe application** named "Innovate for Sustainable Accelerating Systems with Energy Recovery" (iSAS) has been approved and a specific item is the development of an **innovative RF power coupler** for the superconductive linac foreseen in BriXSinO.
- ✓ In 2025 the assembly of all the components of the photoinjector along with the first buncher cavity will be assembled and tested


Facility Poster







Facility Overview List



- Please check your facility
- Send your updates to us
 - BriXSino update on the way

Thanks to all contributions and discussions!

