




**The Joint ESS -J-PARC & SAKURA Workshop
(June 10-12, 2024)**

Plan for Accelerator Development at J-PARC

Hidetomo Oguri

**Accelerator Division
J-PARC Center**

J-PARC Accelerators



● Linac

- **H⁻ beam** acceleration
- Beam energy : **400 MeV**
- Beam current:
50 mA for user operation
60 mA for beam study
(peak current at linac exit)
- Pulse length : < 0.5 ms
- Repetition: 25 Hz

● Rapid Cycling Synchrotron(RCS)


- Charge-exchange injection **H⁻ → H⁺**
- Beam energy : **3 GeV**
- Injection into MR
- Delivery to MLF
- Beam supply to MLF with the beam power of **~1 MW** (in 2024)

● Main Ring Synchrotron(MR)


- Beam energy : **30 GeV**
- Beam power:
760 kW (in 2023) to NU
80 kW (in 2024) to HD

Layout of linac components

- The J-PARC linac consists of an **ion source** and four types of accelerating cavities (**RFQ**, **DTL**, **SDTL** and **ACS**), and is installed in an accelerator tunnel approximately 13 meters underground.
- The RFQ, DTL and SDTL are driven by **324-MHz klystrons**, and the ACS is driven by **972-MHz klystrons**. These klystrons are installed in a 330-m-long room called the klystron gallery at ground level.



Linac beam intensity



Operation history of the linac beam intensity

- In 2008, MLF user operation started with linac beam current of **5mA**.
- In 2009, beam current was increased to **15mA** and operated for about next five year.
- In 2014, after linac upgrade was completed, **30mA** operation started.
- In 2018, **50mA (nominal)** operation was started.

Plan for Accelerator Devel. (MR)



■ for Neutrino experiment:

Beam power increase to 1.3 MW

(Present max. power: 760 kW)

- RF system upgrade
- Reinforcement of capacitor bank for main electromagnet power supply
- Improvement (capacity increasing) of beam dump to facilitate beam tuning
- Beam diagnostics development and upgrade

■ for Hadron experiment:

Beam power 100 kW early achieved

(Present max. power: 80 kW)

- Slow extraction system upgrade to realize low residual radiation
- Replacing extraction devices (extraction septum magnets, Q-magnets) with having large aperture ones (for COMET experiment).




Fig. : MR beam upgrade plan

Plan for Accelerator Devel. (LI/RCS/3NBT)



■ for MLF-TS2 (1.5 MW from RCS):

Linac:

- Increasing the beam intensity of the front-end part
- High power klystron and klystron power supply system to keep high availability

RCS:

- Long lifetime exchange stripper foil
- High performance semiconductor amplifiers for RF system

3NBT:

- Design of beam transport line from RCS to MLF-TS2

■ for Irradiation facility (250 kW from linac):

Linac 50 Hz operation

- System commissioning of 50 Hz operation will be conducted this summer.
- High power klystron and klystron power supply system.
- Beam dividing system.
- Beam monitor upgrade.
- Cooling water system upgrade.

