


# ***High intensity operations of J-PARC accelerators***

**Michikazu Kinsho**

**J-PARC Center**

**Japan Atomic Energy Agency (JAEA)**




# J-PARC Accelerators

## High-intensity proton accelerators

### □ Linac

- length: 249 m
- energy: 181 MeV ( - 2013), 400 MeV (2014 - )
- beam extracted to RCS



### □ Rapid-Cycling Synchrotron (RCS)

- circumference: 348 m
- energy: 3 GeV
- design beam power: 1 MW
- beam extracted to MR  
and Materials and Life Science Experimental Facility



### □ Main Ring (MR)

- circumference: 1,568 m
- energy: 30 GeV
- design beam power:  
750 kW at 1<sup>st</sup> stage , 1300kW at 2<sup>nd</sup> stage for Nu  
100kW for HD
- beam extracted to Neutrino Facility (Nu), or Hadron Facility (HD)









# 400 MeV linear accelerator




## Ion source




A negative hydrogen ion is produced by addition of an electron to a hydrogen atom



Separate-type Drift Tube Linac (SDTL)



Annular Coupled Structure (ACS) linac





The beam is further  
speed) through the

The beam is further accelerated to 400 MeV (71%  
of the light speed) through the ACS section and  
transported to the RCS.



# 3 GeV Rapid-Cycling Synchrotron (RCS)



Electron  
-1



I'm Negative  
hydrogen ion

I'm  
Proton!





# 3 GeV Rapid-Cycling Synchrotron (RCS)









# Main Ring (MR)

The remaining protons are transported to the MR and up to 30GeV



To the Neutrino experimental facility





***History of beam delivery  
from Accelerators to Users***



## 2007

- The **linac** accelerated the beam to a design value of **181 MeV** at that time on January 24<sup>th</sup>, 2007.
- The **RCS** accelerated the beam to a design value of **3 GeV** on October 31<sup>st</sup>, 2007.

## 2008

- The beam extracted from the RCS was transported to the **Neutron production target** on May 30<sup>th</sup>, 2008.
- The beam extracted from the RCS was transported to the **muon production target** on September 26<sup>th</sup>, 2008.
- The **MR** accelerated the beam to a design value of **30 GeV** on December 23<sup>rd</sup>, 2008.

## 2009

- Beam extracted from the MR by slow extraction and transported to the **Hadron Experimental Hall** on January 27<sup>th</sup>, 2009.
- Beam extracted from the MR by fast extraction and transported to the **Neutrino Experimental Hall** on April 23<sup>rd</sup>, 2009.





*The linac accelerated the beam to a design value of **181 MeV** at that time on January 24<sup>th</sup>, 2007.*



## 2007

- The **linac** accelerated the beam to a design value of **181 MeV** at that time on January 24<sup>th</sup>, 2007.
- The **RCS** accelerated the beam to a design value of **3 GeV** on October 31<sup>st</sup>, 2007.

## 2008

- The beam extracted from the RCS was transported to the **Neutron production target** on May 30<sup>th</sup>, 2008.
- The beam extracted from the RCS was transported to the **muon production target** on September 26<sup>th</sup>, 2008.
- The **MR** accelerated the beam to a design value of **30 GeV** on December 23<sup>rd</sup>, 2008.

## 2009

- Beam extracted from the MR by slow extraction and transported to the **Hadron Experimental Hall** on January 27<sup>th</sup>, 2009.
- Beam extracted from the MR by fast extraction and transported to the **Neutrino Experimental Hall** on April 23<sup>rd</sup>, 2009.



*The RCS accelerated the beam to a design value of **3 GeV** on October 31<sup>st</sup>, 2007.*



## 2007

- The **linac** accelerated the beam to a design value of **181 MeV** at that time on January 24<sup>th</sup>, 2007.
- The **RCS** accelerated the beam to a design value of **3 GeV** on October 31<sup>st</sup>, 2007.

## 2008

- The beam extracted from the RCS was transported to **the Neutron production target** on May 30<sup>th</sup>, 2008.
- The beam extracted from the RCS was transported to the **muon production target** on September 26<sup>th</sup>, 2008.
- The **MR** accelerated the beam to a design value of **30 GeV** on December 23<sup>rd</sup>, 2008.

## 2009

- Beam extracted from the MR by slow extraction and transported to the **Hadron Experimental Hall** on January 27<sup>th</sup>, 2009.
- Beam extracted from the MR by fast extraction and transported to the **Neutrino Experimental Hall** on April 23<sup>rd</sup>, 2009.





*The MR accelerated the beam to a design value of **30 GeV** on December 23<sup>rd</sup>, 2008.*

## 2007

- The **linac** accelerated the beam to a design value of **181 MeV** at that time on January 24<sup>th</sup>, 2007.
- The **RCS** accelerated the beam to a design value of **3 GeV** on October 31<sup>st</sup>, 2007.

## 2008

- The beam extracted from the RCS was transported to the **Neutron production target** on May 30<sup>th</sup>, 2008.
- The beam extracted from the RCS was transported to the **muon production target** on September 26<sup>th</sup>, 2008.
- The **MR** accelerated the beam to a design value of **30 GeV** on December 23<sup>rd</sup>, 2008.


## 2009

- Beam extracted from the MR by slow extraction could be transported to the **Hadron Experimental Hall** on January 27<sup>th</sup>, 2009.
- Beam extracted from the MR by fast extraction could be transported to the **Neutrino Experimental Hall** on April 23<sup>rd</sup>, 2009.





# History of MR beam power




***MR***

high repetition rate upgrade




# High impedance rf system

A new type of the magnetic alloy (MA) core, FT3L(made by Hitachi Metal), was developed and adopted to increase shunt impedance of the rf cavity.



Comparison of field gradient of rf cavities for proton synchrotron.

- Performance of cavities depends on core materials: **ferrite** and **MA**.
- Our rf cavity achieved very high field gradient.



The rf cavities installed in the MR tunnel.

**Much Higher intensity proton could be accelerated in J-PARC synchrotrons.**

# Large-scale hardware upgrades for faster repetition rate & higher beam intensity



New main magnet p.s. QDN



Installation of new trans.



New high field FX septum magnets SM30-32




New power amp. for cav#12



New collimator D

- MR had major hardware upgrades for
    - Main magnet power supplies
    - RF system
    - Inj/FX system
    - Collimators, etc.
- with one-year long shutdown period of July 2021- June 2022.




Beam commissioning at the operation cycle of 1.36 s is in progress in parallel to the user operation.



# Achieved stable operation of MR at 800kW for NU

- During the initial machine tuning and operation, various troubles occurred for the updated devices.
- But we accommodated these troubles each time, and **reached** several important milestones after the high-repetition rate upgrade.
  - Started beam operation for users in earnest from the April of 2023.
  - Achieved **760 kW** beam operation in December 2023,
    - exceeding the original design performance of **750 kW**
  - Achieved **800 kW stable user operation** in June 2024 with continuous efforts in both beam tuning & hardware tuning



# Achieved stable operation of MR at 80kW by slow extraction for HD



24/04/19 15:03:28

Run

91

Shot

1789690

at

24/04/19 15:03:25

## Slow Extraction

Duty Factor 56.52 %

5 shots-Ave. 53.75 %

Ext Efficiency 99.520 %

5 shots-Ave. 99.542 %

Spill Length 1.94 sec

5 shots-Ave. 1.95 sec

MR Power 81.32 kW

5 shots-Ave. 81.38 kW


Inj Loss 0.00 W

5 shots-Ave. 0.00 W

Beam On

HD-Run

Destination: HD



## ● We preformed:

- Optics tuning
- Dynamic RF manipulation to suppress beam instability during the de-bunching process at flattop
- Introduction of a diffuser to reduce beam loss at ESS during SX
- Spill feedback tuning ...




Extraction efficiency 99.6%  
Spill duty factor 72%





# History of beam delivery to the MLF



# ***Linac Upgrade***


energy and peak current



# ***Linac energy upgrade***

Energy upgrade (from 181 MeV to 400 MeV) by installing ACS in 2013.

Before installation






# ***Linac energy upgrade***

Energy upgrade (from 181 MeV to 400 MeV) by installing ACS in 2013.

After installation





The linac accelerated the beam to a design value of **400 MeV** on January 17<sup>th</sup>, 2014.






# Linac peak current upgrade

Ion Source and RFQ were replaced in 2014



## Ion source




New



- Filament -> RF-driven
- Cs free -> Cs seeded




## RFQ




- Modified RFQ with beam dynamics design for higher beam current

New




# New front-end system for peak current upgrade

An rf-driven  $H^-$  ion source and RFQ-III for the peak current of 50 mA were tested in a test bench, which was constructed in the linac building, before installed in the tunnel.



Long-term continuous operation results of the new front-end system

50 mA




- ✓ The front-end system was installed in the linac tunnel in summer shutdown of 2014.
- Beam commissioning was started from October 1<sup>st</sup>, 2014.







# History of beam delivery to the MLF




# Latest beam loss mitigation at 1 MW operation in the RCS



Circulating beam intensity measured by the SCT

➤ No beam intensity loss can be seen.



Beam loss signal measured by S-BLM

➤ The beam loss occurs only around during injection.

Beam loss distribution whole the RCS

- Measured beam loss in the RCS at 1 MW integrated from injection to extraction.
- ✓ The beam loss is **80% reduced** from that of 2020 by optimizing stripper foil size, resonance correction, optimizing longitudinal and transverse paintings including and betatron tunes.




- ✓ Estimated beam loss is dominated by the foil scattering beam loss of the circulating beam during injection.
- Corresponds beam loss power is **~0.1 kW**
  - ✓ **Very small** value compared to the collimator capacity of **4 kW**.

## ***J-PARC future plan***



# J-PARC future plan



## ● Neutrino facility

### Hyper-Kamiokande

experiment will be start form 2027, with high power beam from MR. The goal of beam power is 1.3MW.

## ● Hadron facility

- **Hadron hall expansion** will be planed from 2026. We have to realize the beam power of 100kW as soon as possible for hadron experiments.
- **The COMET experiment** with 8GeV bunched beam extracted from MR will be planed in the Hadron Experimental facility.

## ● MLF

has plan to build a **2<sup>nd</sup> target station** in 2030s.

- The beam power of more than 1.5MW has to be realize at energy of 3GeV with 25Hz in the RCS.


## ● Irradiation facility for accelerator driven transmutation experiment.

Beam power of 250kW at the energy of 400MeV with 25Hz are requested from this facility to the linac.

## ***MR developments***

Beam intensity 1.3 MW for Nu / 100kW for HD



# FX beam power projection through 2028



- The beam power will be increased step by step with hardware upgrades,
  - while gradually reducing the **operation cycle**
  - while gradually increasing the **beam intensity**
  - while continuing beam dynamics tuning for **beam loss reduction**.
- We aim to achieve **1.3 MW in 2028** in line with the startup of Hyper-Kamiokande.



# Perspective of the SX operation



Beam study results with two sets of diffusers for low intensity beam (11 kW)


- It was found that installation of diffusers in slow extraction area is effective to reduce beam loss.

- The beam power will be increased to **100 kW** in stages
  - while further **reducing beam loss**, - while further **improving spill duty factor** by
    - improving configuration of diffusers, - introducing new optics with large slippage factor
    - improving spill feedback system, - reducing current ripple of main magnet PS
    - introducing VHF cavity, etc.
- We aim to achieve this **by 2026**.


## ***Developments of Linac and RCS for high intensity beam operation***

Beam intensity **~1.5 MW** is a next goal

# Development of high intensity ion source



Schematic of the RF-driven H<sup>-</sup> ion source




Trend graph of  $I_{H^-}$ ,  $I_{EE}$ ,  $P_{2\text{MHz}}$ , and Cs-valve during 8 hours operation

- We have developed cesiated RF-driven H<sup>-</sup> ion source to realize high intensity.
- The stable operation with **145 mA** and **duty factor of 3.4%** has been performed for **8 hours**.
- This beam has particle distributions in horizontal and vertical phase planes comparable to that used in typical RFQ designs.
- This beam intensity will realize the next generation benchmark H<sup>-</sup> ion source for high intensity and high energy H<sup>-</sup> LINACs.



Ref. : A. Ueno, "Innovative cesiation deriving incredible 145 mA beam from J-PARC cesiated RF-driven H<sup>-</sup> ion source", J. Phys.Conf. Series, 2743, 012001 (2024).




# New cavity for the RCS



The beam power of the RCS had been limited by the cavity anode power supply current.



The new cavity solved this issue.



The new cavity has the capability to realize **2 MW** beam power in the RCS.


# Reduction of RCS kicker magnet impedance effect

We proposed a scheme for suppressing the kicker impedance by using diodes and resistors, thereby demonstrating the effect on the kicker impedance reduction, because simulations have shown that reducing the impedance of the kicker magnets is necessary for stable acceleration of particles with high intensities more than 1 MW in the RCS.



- We have demonstrated that the special diodes with resistors **can suppress the beam instability** by reducing the kicker impedance.
- This system makes it possible to stably accelerate more than 1MW beam in the RCS.
- This system have a negligible effect on the extracted beam from the RCS.
- The J-PARC RCS must be operated with a repetition rate of 25 Hz, which urged us to consider special diodes that are tolerant to heating.
- Enhanced durability of the prototype diodes and resistors for the 25Hz operation was also realized.


Power supply for  
kicker magnet




Ref. : Y. Shobuda et al., Demonstration of a kicker impedance reduction scheme with diode stack and resistors by operating the 3-GeV rapid cycling synchrotron of the Japan Proton Accelerator Research Complex, *Phys. Rev. Accel. Beams* 26, 053501 (2023)

# Beam study for 1.5 MW beam power

## Injection pulse (from linac)




## Extraction at 0.8 GeV



## Acceleration up to 0.8 GeV:

- ✓ Due to limitation of the RF system for acceleration up to 1 GeV,
  - ✓ because the RF cavities are not yet fully replaced to new ones.
- we extracted the beam at 0.8 GeV ( $\sim 6 \text{ ms}$ ) to avoid any RF trips.
- ✓ Enough to check the beam loss as occurring at lower energy



- The beam loss occurs only around injection energy localizing at the collimator area.
- The beam loss power is **only 0.2 kW**
  - very small value compared to the collimator capacity of **4 kW**.
- We can't confirm it at **1.5 MW** now as acceleration was done up to 0.8 GeV.
- ✓ Simulation results shows **that no beam instability occurs at 1.5 MW** with impedance reduced to half by diodes installed at the extraction kicker magnets.



# Summary

- Since its operation, the J-PARC accelerator facility has increased beam intensity through the development of various components and careful beam tuning.
- This is the great effort of the accelerator team members, so I would like to pay tribute to them.
- I would also like to thank all of users for the tremendous support and encouragement for us.

## Mission of J-PARC

- **J-PARC will continue to evolve and become a facility that can continuously produce research results, and to be an internationally attractive, state-of-the-art facility.**
  - As a global common facility, we will constantly pursue **the world's highest intensity and highest quality quantum beams**, supply them to all users and make them a source of new breakthroughs.
    - ✓ New technologies have expanded mankind's knowledge and created new breakthroughs.
- **And contribute to the welfare and prosperity of human society through research and development results**
  - We develop those world-leading tools ourselves, take advantage of the benefits we have, use them ourselves, and create new breakthroughs.

**The J-PARC accelerator facility will continue to evolve to satisfy the requirements of all users.**